

Cincinnati Fire Department Fire Training Supplement DRILL BOOK

TOPIC TITLE:

SECTION #8 Minimum Company Standards

Date: January 2006

Section #: 8 Elevated Master Stream Deployment

Total # of Pages: 2

Topic #: 7

<u>Title:</u> Elevated Master Stream Deployment

<u>Task Level:</u> Engine Company and Ladder Company (8 personnel)

Equipment Needed: Engine Company, Ladder Company, Ladder Pipe Hose and Nozzle and Control

Ropes, 5" Supply Line, Hydrant, Safe location without traffic safety hazards

Recommended Time: 5 minutes

Reference: NFPA 1410, 2000 Edition, Training for Initial Scene Operations

Instruction:

• Stage Engine Company, Ladder Company and assigned personnel away from fire area. When personnel are ready, give signal and proceed to the fire area.

• TIME STARTS WHEN 1st APPARATUS STOPS AT FIRE ARFA

• Engine Company Forward Lay 5" supply line a distance of 300 feet to simulated fire area at the ladder company

 Ladder Company sets aerial, attaches nozzle, and flakes hose on the aerial ladder.

• Hose must be strapped

Ladder is raised to full extension at a 60 degree angle

• Officer orders water started when it is hooked up

 Ladder officer request 500 GPM to be supplied to the ladder pipe

• FAO transfers from the tank to the hydrant

Stop the time when all lines are supplied and flowing properly

Evaluation: Pass or Fail

Re-Testing: If companies fail to meet the required time limit or are stopped due to unsafe

acts they will be given an additional opportunity to pass the evolution in one

month.

<u>Critical Criteria:</u> Failure to meet time limit

Failure to wear full PPE

Failure to supply proper GPM to each hose line

Failure to transfer from tank to hydrant supply properly. Up to 10 second

interruption in water supply deliver is acceptable

Failure to strap ladder pipe hose

Unsafe acts as interpreted by the evaluator



Cincinnati Fire Department Fire Training Supplement DRILL BOOK

SECTION #8
Minimum
Company
Standards

Date: January 2006

Section #: 8

TOPIC TITLE: Elevated Master Stream Deployment

Total # of Pages: 2
Topic #: 7

Topic #7 Description:

